BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/08/2020-21 Dated: 26-11-2020

APPROVED TENDER SCHEDULE –'B'

Item 14

Name of Work :-Improvements to roads and drains at Allalasandra Ambedkarnagara Kanaka nagara and LBS nagara in ward no:04

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri YELAHANKA ASHWATHAIAH DHANASHEKAR	
				Rate	Rate in Words
1	Removing and refixing stone slabs of drains and pointing in CM (1:3)	Sqm	517.44	116.81	One Hundred Sixteen Paise EightyOne Only
2	KSRB 300-1. : Earthwork Excavation by manual means for roads, drains and similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per Specifications with all lead and lift as per direction of Engineer in charge.	Cum	1352.91	225.94	Two Hundred TwentyFive Paise NinetyFour Only
3	KSRB M2100-10: Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @ 0.89 cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centring complete as per specifications with all lead and lift as per direction of Engineer in charge.	Cum	207.69	5690.28	Five Thousand Six Hundred Ninety Paise TwentyEight Only

Y. A. Dhanekar

	Providing and laying in position plain cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.43 cum machine mixed, well compacted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execuding cost of steel as per Morth Specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per Specifications with all lead and lift as per direction of Engineer in charge.	Cum	341.96	7420.17	Seven Thousand Four Hundred Twenty Paise Seventeen Only
5	KSRRB M2300-14: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour HOM of machinery complete as per specifications with all lead and lift as per direction of Engineer in charge.	Tonne	22.31	68266.72	SixtyEight Thousand Two Hundred SixtySix Paise SeventyTwo Only
6	Providing and Fixing RCC pre cast cover Slab 100mm thick for drain made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement inciuding form work, lift charges, curing and concrete finished on both sides etc., Complete As per drawing and direction of Engineer IN charge.	Sqm	1130.01	2452.68	Two Thousand Four Hundred FiftyTwo Paise SixtyEight Only
7	Providing and Fixing RCC pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work, laid and lift charges, curing and concrete finished surfaces on both sides etc., complete. As per Engineer IN charge.	Sqm	66.60	5686.19	Five Thousand Six Hundred EightySix Paise Nineteen Only
8	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished cutting , including form work, curing, including cost of all materials, labour, hire charges of machinery, loading and unloading, laid and lift, transportation etc., complete.	Nos	662.00	453.89	Four Hundred FiftyThree Paise EightyNine Only

Y. A. Chavelekar

	Painting Two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	104.30	89.00	EightyNine Only
10	KSRRB M200-24: Dismantling of cement concrete pavement by mechanical means using pneumatic tools breaking to pieces not execuding 0.02 cum in volume and stock pilling at designated locations and disposal of dismantled locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperatly complete as per specifications with all lead and lift as per directon of engineer in charge.	cum	35.64	1021.60	One Thousand TwentyOne Paise Sixty Only
11	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum, Coarse and fine aggregate conforming to IS: 383-2016, With Superplastizer at 3 Lts conforming to IS 9103-2008 mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, seperation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing with all lead and lift as per the direction of Engineer In charge.	Cum	31.10	5468.90	Five Thousand Four Hundred SixtyEight Paise Ninety Only

Y. A. Dhavalkar
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.